

ОБЕМ НА АСФАЛТОВЕТОНА

Обект: граница община Самуил - с.Хума

Проектна скорост : 50 км/ч

Вид нивелета : прави и кв. параболи

Участък от км. 0.00 до км. 1462.15

Таблица 6

N	Километър	Име	Осн.Пл	Подосн.	Гор.Пл	Площ	Обем	Н екв.
	(m)	Точка	(м^3)	(м^3)	(м^3)	(м^2)	(м^3)	(cm)
114	940.00	89	0.00	0.00	0.00	0.0	0.00	0.00
115	951.00	90	7.20	2.25	2.22	55.0	11.67	21.21
116	961.93	91	14.48	4.49	4.42	109.6	23.39	21.33
117	971.01	92	21.07	6.35	6.25	155.1	33.67	21.72
118	981.66	93	28.66	8.53	8.40	208.3	45.60	21.89
119	992.08	94	35.27	10.67	10.50	260.4	56.43	21.67
120	1001.94	95	41.51	12.69	12.49	309.7	66.69	21.53
121	1011.90	96	47.82	14.73	14.50	359.5	77.05	21.43
122	1022.03	97	54.24	16.80	16.54	410.2	87.58	21.35
123	1033.36	98	61.42	19.12	18.82	466.8	99.36	21.29
124	1045.13	99	68.88	21.53	21.19	525.7	111.60	21.23
125	1055.24	100	75.29	23.60	23.23	576.2	122.12	21.19
126	1078.46	101	90.76	28.36	27.91	692.3	147.04	21.24
127	1082.05	НК10	93.52	29.09	28.64	710.3	151.25	21.30
128	1089.09	102	100.85	30.53	30.06	745.4	161.44	21.66
129	1099.83	103	111.96	32.73	32.22	799.1	176.92	22.14
130	1110.43	104	120.81	34.90	34.36	852.2	190.07	22.30
131	1120.98	105	131.11	37.06	36.49	904.9	204.66	22.62
132	1131.99	106	143.14	39.32	38.71	959.9	221.16	23.04
133	1140.18	107	151.86	41.00	40.36	1000.9	233.21	23.30
134	1141.91	СК10	153.61	41.35	40.71	1009.6	235.67	23.34
135	1150.83	108	161.05	43.18	42.50	1054.1	246.73	23.41
136	1162.12	109	168.48	45.49	44.78	1110.6	258.75	23.30
137	1172.51	110	175.07	47.62	46.87	1162.6	269.56	23.19
138	1183.69	111	182.15	49.91	49.13	1218.4	281.19	23.08
139	1195.02	112	189.37	52.23	51.41	1275.1	293.01	22.98
140	1201.77	КК10	194.61	53.61	52.77	1308.9	300.99	23.00
141	1205.56	113	198.07	54.39	53.54	1327.8	306.00	23.05
142	1215.58	114	205.95	56.44	55.56	1377.9	317.94	23.07
143	1225.52	115	212.36	58.47	57.56	1427.6	328.40	23.00
144	1235.93	116	218.96	60.61	59.66	1479.7	339.22	22.93
145	1246.70	НК11	225.78	62.81	61.83	1533.5	350.42	22.85
146	1247.07	117	226.01	62.89	61.91	1535.3	350.81	22.85
147	1257.63	118	232.71	65.05	64.03	1588.2	361.79	22.78
148	1263.62	СК11	236.50	66.28	65.24	1618.1	368.02	22.74
149	1266.95	119	238.61	66.96	65.91	1634.7	371.48	22.72
150	1269.74	120	240.53	67.53	66.48	1648.7	374.54	22.72
151	1275.27	121	244.51	68.66	67.59	1676.4	380.76	22.71
152	1280.54	КК11	248.00	69.74	68.65	1702.7	386.40	22.69
153	1287.06	122	252.36	71.08	69.97	1735.3	393.40	22.67
154	1296.94	123	259.36	73.10	71.96	1784.7	404.42	22.66

155	1299.02	HK12	260.80	73.53	72.38	1795.1	406.70	22.66
156	1305.75	CK12	265.15	74.91	73.74	1828.8	413.79	22.63
157	1309.86	124	267.75	75.75	74.56	1849.3	418.06	22.61
158	1312.48	KK12	269.41	76.28	75.09	1862.4	420.79	22.59
159	1321.45	125	275.10	78.12	76.90	1907.2	430.12	22.55
160	1333.16	126	282.52	80.52	79.26	1965.8	442.30	22.50
161	1344.12	127	289.46	82.76	81.47	2020.6	453.69	22.45
162	1357.26	128	297.79	85.45	84.12	2086.3	467.36	22.40
163	1368.38	129	304.83	87.73	86.36	2141.9	478.92	22.36
164	1379.87	130	312.11	90.09	88.68	2199.3	490.87	22.32
165	1389.77	131	318.38	92.11	90.67	2248.9	501.17	22.29
166	1392.31	HK13	319.99	92.63	91.19	2261.6	503.81	22.28
167	1400.18	132	324.98	94.24	92.77	2300.9	512.00	22.25
168	1409.88	133	331.13	96.23	94.73	2349.4	522.08	22.22
169	1416.57	CK13	335.36	97.60	96.08	2382.8	529.04	22.20
170	1421.49	134	339.58	98.61	97.07	2407.4	535.25	22.23
171	1432.26	135	357.93	100.81	99.24	2461.3	557.98	22.67
172	1438.09	136	372.38	102.07	100.47	2491.9	574.93	23.07
173	1440.83	KK13	378.69	102.68	101.08	2507.0	582.45	23.23
174	1445.27	HK14	387.26	103.68	102.06	2531.4	593.00	23.43
175	1450.22	137	394.68	104.79	103.16	2558.6	602.64	23.55
176	1450.86	CK14	395.43	104.94	103.30	2562.1	603.67	23.56
177	1456.44	KK14	400.49	106.19	104.54	2592.8	611.22	23.57
178	1462.15	138	404.45	107.48	105.80	2624.2	617.73	23.54